COST ESTIMATION OF A 40 FEET BY 8 FEET CARAVAN COLUMN CONSTRUCTION FOR INSTALLATION

① FOUNDATION BASKET RODS (12mm)

For a 3ft(w) by 6ft(L) x 3ft(H) basket
3ft(w) by 3ft(L) x 3ft(h) basket
provide 3ft(h) by 6ft(w) x 6ft(L) basket

₦9800 X 20 = ₦196,000

provide 20 pieces of 12mm Rods

② COLUMN RODS (16mm)

For a 3ft(w) by 6ft(L) x 3ft(h)
3ft(w) by 3ft(L) x 3ft(h)
3ft(h) x 6ft(w) x 6ft(L)

₦18,000 X 15 = ₦270,000

provide 15 pieces of 16mm rods.

③ STYRUP / TIE ROD (8mm)

For the 6 columns / baskets

₦4500 X 15 = ₦67,500

provides 15 pieces of 8mm rods

④ Binding Wires
1 Bundle ₦35,000

⑤ BOARDS
1 x 12 provides 60 pieces — ₦3000 X 60 = ₦180,000
1 x 3 provides 25 pieces — ₦1400 X 25 = ₦35,000

⑥ Nails
3 inches. provides Half a bag — ₦17,500
2 inches provides Half a bag — ₦17,500

Scanned by TapScanner

⑦ FINE AGGREGATE (SAND)

· For all the 6 trips ~~both~~ foundation level to finishing

provides 15 mini Jinar truck. — ₦8,000 X 15 = ₦120,000

⑧ ORDINARY PORT-HAND CEMENT FOR BOTH BLINDING & COLUMN

provides 80 bags — ₦10,500 X 80 bags = ₦840,000

⑨ AGGREGATE (GRANITE 20mm)

provides 1 mini tipper = 1250 bags — ₦800 X 900 bags — ₦720,000

⑩ ~~2~~ FOR LABOUR

⑩ 2 Capenters (10,000 daily per person) ₦10,000
₦20,000 X 3 Days — ₦60,000

⑪ 2 iron benders (7,000 ~~person~~ daily per person) ₦7,000
₦14,000 X 3 Day = ₦42,000

⑫ 2 Merson (10,000 daily per person) ₦10,000
₦20,000 X 10 Days — ₦200,000

⑬ Casters 6 person at 1,800 per bag of Cement)
₦1800 X 80 bags = ₦144,000

⑭ Diggers - ~~6,000~~ 7,000 naira trench
₦7000 X 7 holes pit = ₦49,000

⑮ PROFESSIONAL FEE ENGINEER | SUPERVISORY WORK

₦40,000 daily (Naira)
₦40,000 X 14 days = ₦560,000

LABOUR TOTAL — ₦1,055,000

Scanned by TapScanner

(16) Boat Transport — ₦500,000

(17) Loading & Off Loading — ₦1,000,000

TOTAL = ₦5,053,500

Scanned by TapScanner